Eötvös Loránd University

Faculty of Informatics

Dept. of Artificial Intelligence

# AK&VEN: An Online Shop for a Family Sock Business with a Price-Negotiating Assistant Bound by the Owners' Limits

*Supervisor:*
Guettala Walid
PhD Candidate

*Author:*
Nurmuhammed Kanybekov
Computer Science BSc

*Budapest, 2026*

# Abstract

This thesis presents AK&VEN, the online shop of a family business that has sold Korean-made socks from container 70-E at Dordoi Bazaar in Bishkek, Kyrgyzstan, since 2018. At the bazaar the price is agreed rather than read from a label, families buy for everyone at once, and shops from the regions buy by the case. The shop brings these habits online instead of replacing them with a fixed price tag: customers mix any socks and the price per pair falls with the size of the whole bag, plan one set for the whole family, ask for a better price in a chat, and collect their order at the stall with a pickup code or have it delivered to four countries.

The central technical question is how a language model can be allowed to talk about money without being trusted with it. The design separates talking from deciding. The assistant, either a rule-based negotiator or a large language model, only proposes a discount; a small deterministic component, the `PolicyValidator`, clamps every proposal to a limit the owners set for each product, which the model never sees. The check is repeated at checkout and by the database, and every proposal is recorded beside the discount allowed. A model that is confused, flattered or manipulated therefore cannot change what a customer pays.

The system is a single installable progressive web application in English, Russian and Kyrgyz, built with React and TypeScript, on top of one Spring Boot API with role-based access for customers, staff, owners and a super admin, and a PostgreSQL database whose constraints repeat the most important business rules. The thesis documents the requirements, the interface for each role, the architecture, the data model, the pricing and negotiation logic, security, and more than 470 automated tests. A recorded run of a live model on sixteen simulated customers shows that neither assistant ever priced a sock below the owners' limit.

# Contents


**1 Introduction** **1**

1.1 Background . . . . . 1

1.2 Related work . . . . . 2

1.3 Motivation . . . . . 3

1.4 Thesis objective . . . . . 3

1.5 Research questions . . . . . 4

1.6 Scope . . . . . 4

1.7 Structure of the thesis . . . . . 5

**2 Specification** **6**

2.1 Software perspective . . . . . 6

2.2 User classes and characteristics . . . . . 7

2.3 Use cases . . . . . 7

2.3.1 Representative scenarios . . . . . 9

2.4 Functional requirements . . . . . 10

2.5 Non-functional requirements . . . . . 12

2.6 Constraints . . . . . 13

2.7 Assumptions and dependencies . . . . . 13

2.8 User interface plan . . . . . 14

**3 User documentation** **15**

3.1 System requirements . . . . . 15

3.1.1 Server . . . . . 15

3.1.2 Client . . . . . 16

3.2 Installation and start . . . . . 16

3.2.1 Demo accounts . . . . . 16

3.2.2 Configuration . . . . . 16

3.3 The shop . . . . . 17

3.3.1 Everywhere: the header, languages, currencies and the footer . 17
3.3.2 The home page . . . . . 18
3.3.3 The shelves: browsing and filtering . . . . . 19
3.3.4 A product . . . . . 21
3.3.5 Asking for a better price . . . . . 22
3.3.6 The fitting room, the size guide and the sock finder . . . . . 23
3.3.7 The family planner and gift boxes . . . . . 24
3.3.8 The bag, checkout and payment . . . . . 26
3.3.9 Orders and pickup . . . . . 27
3.3.10 The account . . . . . 28
3.3.11 Wholesale and company gifts . . . . . 29
3.3.12 Finding the stall . . . . . 31
3.3.13 On a phone . . . . . 32
3.4 The administration . . . . . 32
3.4.1 For the whole team . . . . . 32
3.4.2 For the owners . . . . . 37
3.4.3 For the super admin . . . . . 38
3.5 Troubleshooting . . . . . 39
3.6 Limitations . . . . . 40

**4 Developer documentation 41**
4.1 Overview . . . . . 41
4.2 Technology stack . . . . . 43
4.3 Repository orientation . . . . . 43
4.4 System design . . . . . 44
4.4.1 Layers inside the backend . . . . . 44
4.4.2 Roles . . . . . 44
4.5 Data model . . . . . 45
4.5.1 Integrity in the database . . . . . 48
4.6 REST API . . . . . 48
4.7 Security . . . . . 50
4.8 Pricing and the PolicyValidator . . . . . 51
4.8.1 Collection pricing . . . . . 51
4.8.2 The validator . . . . . 51

4.9 The negotiation assistant . . . 53
4.9.1 Design . . . 53
4.9.2 Defences of the language-model negotiator . . . 55
4.10 Orders, stock and payment . . . 56
4.11 Further domain features . . . 57
4.12 Frontend . . . 59
4.12.1 Structure . . . 59
4.12.2 Design system . . . 60
4.12.3 State and data flow . . . 60
4.13 Running and building . . . 60
4.14 Design trade-offs and known limitations . . . 61

**5 Testing and evaluation 62**
5.1 Testing strategy . . . 62
5.2 Backend tests . . . 63
5.3 Frontend tests . . . 65
5.4 The browser journey . . . 65
5.5 Evaluation of the two assistants . . . 66
5.5.1 Method . . . 66
5.5.2 Results . . . 67
5.5.3 Discussion . . . 67
5.6 Requirements coverage . . . 68

**6 Conclusions and future work 69**
6.1 Conclusion . . . 69
6.2 Answers to the research questions . . . 69
6.3 Future work . . . 70
6.4 Final remarks . . . 71

**Acknowledgements 72**

**Bibliography 72**

**List of Figures 76**

**List of Tables 78**

**List of Codes** **79**

# Chapter 1

# Introduction

## 1.1 Background

AK&VEN is a family brand of Korean-made socks. The name joins the first letters of my parents' names, **AK**ylbek and **VEN**era, with an ampersand drawn as a heart. My family has traded at Dordoi Bazaar in Bishkek since the early 2000s and has sold socks there since 2018, from a shipping container numbered 70-E. Dordoi is one of the largest markets in Central Asia: thousands of containers stacked in long rows, where families shop for the season and traders from the regions of Kyrgyzstan, from Kazakhstan, Uzbekistan and Russia buy goods for their own shops.

Three habits shape how socks are sold there, and every one of them is missing from an ordinary online shop:

- **The price is agreed, not read.** A customer asks, the seller answers, and the price moves with the quantity, the season and the relationship. A fixed price tag feels cold, and a discount code feels like a trick.
- **People buy for the whole family.** One visit covers the father, the mother and the children, each in a different size; the larger the set, the lower the price per pair.
- **Shops buy by the case.** A case holds about 240 pairs in packs of 10 or 12, often mixed, and the price is given on request because it follows the dollar rate, the factory price and the delivery.

This thesis builds the brand's online shop so that these habits can continue online: a customer can ask for a better price in a conversation, plan one order for

the whole family, mix any socks to reach a lower price step, and collect the order at the container or have it delivered. Shops and companies can build a case and send a request that the family answers.

## 1.2 Related work

**E-commerce platforms.** General platforms such as the open-source Shopizer [1], Medusa [2] and Saleor [3] offer catalogues, carts, orders and an administration interface. Their architecture was a model for this project in two respects: a single API serves both the shop and the administration, and the administration is only another client of that API with more rights. They assume fixed prices, however, with discounts expressed as coupons or price lists; none of them treats the price as the result of a conversation, and they are built for multi-tenant scale that a single family stall does not need.

**Negotiation dialogue.** Automated negotiation has been studied in natural-language processing for years. Lewis et al. [4] trained end-to-end models to negotiate the division of items and found that they learned to deceive; He et al. [5] separated the negotiation *strategy* from the *generation* of the sentences, which made the agents' behaviour more controllable. This thesis follows the same separation in an engineering setting: the strategy (how much may be given) is fixed by deterministic code and the owners' settings, and the language model is used for the conversation and a proposal only.

**Reliability of language-model applications.** Large language models follow instructions that arrive in their input, including instructions hidden in user text. Greshake et al. [6] showed that applications which let model output drive actions can be taken over by such prompt injection, and the OWASP Top 10 for LLM applications [7] lists prompt injection, sensitive information disclosure and excessive agency among the main risks. The common advice is to treat model output as untrusted input, to keep secrets out of the prompt and to limit what the model can cause. AK&VEN applies all three to money: the model never sees the limit or the cost price, its proposal is validated by code, and it cannot state a price in its own words.

**Grounding.** Retrieval-augmented generation [8] grounds model answers in retrieved documents rather than in the model's general knowledge. The assistant here receives the facts of the product being discussed (fabric, care, origin, pack size, stock, the public price ladder) selected for the question; the database already has a vector table (pgvector [9]) prepared for embedding-based retrieval in future work.

**Progressive web applications.** A progressive web application [10] is a website that can be installed like an app and can keep working offline with a service worker. For customers at a bazaar with an unreliable mobile connection this matters more than a native app store presence, and one application can serve customers and staff.

## 1.3 Motivation

The motivation is practical and personal. My parents' customers already write to them on WhatsApp and Telegram to ask for prices, sizes and whether a model is still in stock; the answers depend on who is free to reply, and nothing is kept in one place. An online shop would let customers see the whole assortment, choose sizes from the shop's own size chart and pay in advance, and let the family see orders, stock and requests in one list.

The difficulty is that bargaining is part of the brand, and a language model is the obvious tool for a conversation in three languages, but it is not safe to let a model decide prices. A shop that can be talked into a 90% discount loses money; a shop that refuses to talk is not Dordoi. The thesis is about resolving that tension with a design in which the model may talk freely while the price stays under the owners' control.

## 1.4 Thesis objective

The objective is to design, implement, test and evaluate a complete online shop for AK&VEN in which:

- customers can browse, choose sizes and colours, plan a family set, ask for a better price, pay and collect or receive their order, in English, Russian or Kyrgyz, on a phone, a tablet or a laptop;

- the owners and staff manage the catalogue, stock, prices, orders, requests and settings in an administration interface in the same three languages;
- no price below the owners' limit can ever reach an order, whatever the assistant says, and this guarantee is shown by automated tests and by an evaluation on simulated customers.

## 1.5 Research questions

**RQ1.** Can a language model hold a price negotiation for a real shop while a deterministic component guarantees that no discount above the owners' limit is ever applied?

**RQ2.** How does a language-model negotiator compare with a rule-based one on the same simulated customers, in terms of discounts given, sales made and how often the limit had to step in?

**RQ3.** Can the bazaar's habits (bargaining, family sets, price steps by quantity, wholesale by the case) be expressed in an online shop without making it harder to use than an ordinary one?

## 1.6 Scope

Built in this thesis: the shop and the administration as one progressive web application; the REST API with authentication and four roles; the catalogue with sections, cuts, colours, sizes, pictures and stock; collection pricing; the negotiation assistant with a rule-based and a language-model implementation; cart, checkout with a *simulated* Apple Pay and Google Pay wallet, pickup with a code and delivery areas with fees and times; family profiles, gift boxes, reviews, saved socks, wholesale requests and saved customer details; an audit log; the test suite; and deployment with Docker Compose and continuous integration.

Not built, on purpose: a real payment provider (no money moves), e-mail and SMS notifications, taxes, a second payment rail through a Kyrgyz bank, demand forecasting and synchronisation with the family's messenger chats. These are discussed as future work in Chapter 6.

## 1.7 Structure of the thesis

Chapter 2 specifies the system: its users, use cases, and functional and non-functional requirements. Chapter 3 is the user documentation: how to install and start the shop, and how customers, staff, owners and the super admin use it. Chapter 4 is the developer documentation: the architecture, the data model, the API, security, the pricing and negotiation logic, and the design of the frontend. Chapter 5 describes how the system is tested and presents the evaluation of the two assistants. Chapter 6 answers the research questions and lists future work.

# Chapter 2

# Specification

This chapter defines what the system must do. It was written first as the requirement analysis of the first milestone and extended as the project grew; the requirements below are the ones the final program implements. Chapter 5 shows, for each of them, the automated test that demonstrates it.

## 2.1 Software perspective

AK&VEN is a new, self-contained web system: one server application with its database, and one web application that runs in the browser and can be installed on a phone or a computer. It does not replace the stall; it extends it. The stall remains the place where orders are collected and where the stock is kept, and the shop's data (the address of the stall, the opening hours, the contacts, the prices and the size chart) is entered by the owners in the administration rather than written into the code.

## 2.2 User classes and characteristics

| User | Description |
|---|---|
| Visitor | Anyone who opens the shop. Browses the catalogue, uses the size guide, the fitting room and the family planner, fills the bag, and sends a wholesale request, all without an account. |
| Customer | A visitor with an account. Can also check out, ask the assistant for a better price, keep a family profile, saved socks and contact details, follow orders, write reviews and wait for sold-out options. |
| Staff | An employee of the stall. Manages products, stock and orders, hands orders over at the stall, moderates reviews and answers wholesale requests; cannot change prices or the owners' limits. |
| Owner (admin) | Akylbek and Venera. Everything staff can do, plus the limits per product, the price ladder, the exchange rates, delivery areas, contacts, opening hours, the size chart and customer accounts. |
| Super admin | The person who runs the installation. Everything an owner can do, plus the team's accounts, the choice of assistant and the audit log. |
| Assistant | Not a person: the negotiator called by the chat, either rule-based or a language model. Its behaviour and limits are part of the specification, not only of the implementation. |
| Payment provider | The wallet (Apple Pay or Google Pay) that turns a card into a one-time token. Simulated in this thesis. |

Table 2.1: Users of the system

The customers are families and traders from Kyrgyzstan and the neighbouring countries. Many of them shop on a phone, often with a weak connection, and read Russian or Kyrgyz more comfortably than English. The owners are not technical users: the administration must use plain words, their language and few steps.

## 2.3 Use cases

Figures 2.1 and 2.2 show the use cases of the customer and of the shop team. The most important one, *Negotiate price*, involves the assistant as a secondary actor: the customer talks, the assistant proposes, and the system decides.





Figure 2.1: Use cases of visitors and customers





Figure 2.2: Use cases of the staff, the owners and the super admin

### 2.3.1 Representative scenarios

**A family set.** Aida needs socks for her husband (shoe size 43), herself (38) and her son (32). In the family planner she adds the three of them; the shop works out the sock size of each from its own size chart and shows the price step reached by the 15 pairs. She opens the shop with these sizes, fills the bag, pays with her phone's wallet and receives a six-digit pickup code. At the stall she says the code and the last four digits of her phone number, and Venera hands the bag over.

**Bargaining.** A customer opens a sock and writes "Can you do 50% off for 10 pairs?". The assistant answers in the customer's language with an offer. Whatever it proposes, the offer shown is at most the limit the owners set for that sock; it is kept for 24 hours, applies only to at least the negotiated number of pairs, and can be used once.

**A shop from Osh.** A shop owner builds a case of 240 pairs from the shelves of men's, women's and children's socks, writes the shop's name and a WhatsApp number, and sends the request. The shop answers with a reference number; the request appears in the family's inbox, where they reply with one tap in the customer's own messenger.

## 2.4 Functional requirements

Table 2.2 lists the functional requirements. FR-1 to FR-14 come from the first milestone; FR-15 to FR-26 were added as the shop grew.

| ID | Requirement |
|---|---|
| FR-1 | List the products with their variants (size, colour, pack), price and stock, filterable by audience, section, cut, size, colour and stock. |
| FR-2 | Let a visitor fill a bag without an account; the bag survives a reload and works offline. |
| FR-3 | Accept a negotiation message about a product from a signed-in customer and return the assistant's answer, in the customer's language, as part of a conversation. |
| FR-4 | Ground the assistant's answer in the product's real data (fabric, care, origin, pack, stock, price ladder), not in the model's general knowledge. |
| FR-5 | Check every proposed discount with a deterministic validator against the product's limit before it can be shown, stored or charged; check it again at checkout. |
| FR-6 | Record the proposed and the allowed discount of every negotiation. |
| FR-7 | Take payment only through the wallet interface; never receive or store card numbers. |
| FR-8 | Create a paid order only with a confirmed payment reference. |
| FR-9 | Require authentication for staff and owner actions; staff cannot change prices or limits. |
| FR-10 | Let the team create, edit, remove and restore products, variants, pictures and stock. |
| FR-11 | Restrict cost price and limit changes to owners. |

| ID | Requirement |
|---|---|
| FR-12 | Show the negotiations with both numbers, and a dashboard of offers, limits applied and sales. |
| FR-13 | Record an audit entry (who, what, before, after) for every change to the catalogue, prices, orders, accounts and settings. |
| FR-14 | Let the super admin manage the team's accounts and read the audit log. |
| FR-15 | Price a bag as one collection: a minimum order and a ladder of discounts by the number of pairs in the whole bag, set by the owners. |
| FR-16 | Offer pickup at the stall with a one-time code, a courier in Bishkek and the Chui region, and cargo carriers to the regions, KZ, UZ and RU (paid to the carrier on receipt where the owners say so), each with a fee, a free-from amount, a time and a note set by the owners. |
| FR-17 | Let customers keep a family profile (names, roles, shoe sizes, birthdays) and derive the sock size from the shop's size chart. |
| FR-18 | Let customers build a gift box (box, ribbon, card) that is packed at the stall. |
| FR-19 | Accept reviews only from customers who received the product, and publish them after approval. |
| FR-20 | Let customers wait for a sold-out option and show the owners who is waiting. |
| FR-21 | Accept wholesale and company requests without an account, give a reference, and show them to the team in an inbox with statuses. |
| FR-22 | Remember a customer's contact and delivery details on request, fill them in at checkout, and forget them on request. |
| FR-23 | Show the shop, the administration and all messages in English, Russian and Kyrgyz, with prices in US dollars, Kyrgyz som or Russian roubles at rates the owners set. |
| FR-24 | Show whether the stall is open now in Bishkek time, its hours and how to find it. |
| FR-25 | Let the super admin switch the assistant between the rules and the language model at run time, try it, and repeat the evaluation. |
| FR-26 | Export the orders of a period as a spreadsheet file for the owners. |

| ID | Requirement |
|---|---|
| FR-27 | Let customers order without an account, with an email address, and open, cancel and find their order again through a private link. |
| FR-28 | Email customers in their language when an order is confirmed, handed over and cancelled, and when a wholesale request is received; keep every email readable by the team, and keep the shop working without a mail server. |

Table 2.2: Functional requirements

## 2.5 Non-functional requirements

| ID | Category | Requirement |
|---|---|---|
| NFR-1 | Security | Passwords are stored only as BCrypt hashes. |
| NFR-2 | Security | Every endpoint enforces the roles; there is one API, not a separate administration backend. |
| NFR-3 | Security | Customer text sent to the assistant is untrusted; no discount reaches an order without the validator. |
| NFR-4 | Security | No card data is received, stored or logged. |
| NFR-5 | Reliability | The bag works offline; prices are always recomputed by the server. |
| NFR-6 | Performance | An assistant answer arrives within a conversational time (target: under about 5 seconds). |
| NFR-7 | Maintainability | Every change by the team can be reconstructed from the audit log alone. |
| NFR-8 | Testability | The validator and the pricing are testable without the language model; the build fails under 80% line coverage. |
| NFR-9 | Portability | One installable PWA serves customers and the team through role-gated routes. |
| NFR-10 | Operability | Build and tests run automatically in CI on every push. |

| ID | Category | Requirement |
|---|---|---|
| NFR-11 | Usability | The shop works on phones, tablets and laptops; text meets WCAG 2.2 AA contrast; pages pass automated accessibility rules. |
| NFR-12 | Integrity | The most important rules (stock never below zero, an allowed discount never above its proposal, a paid order has a payment reference) are also enforced by database constraints. |

Table 2.3: Non-functional requirements

## 2.6 Constraints

- **Technology:** Java 17 and Spring Boot 3.5 for the server, PostgreSQL 16 with pgvector for the data, React 18 with TypeScript for the client, Docker Compose for running the whole system.
- **Time:** the ELTE milestones (requirements on 25 September, prototype on 20 October, final program on 10 November, draft on 22 November, submission on 1 December 2026).
- **Business:** there is no agreement with a Kyrgyz payment provider, so payment goes through a wallet interface with a simulated implementation; no real money moves.
- **Privacy:** real phone numbers, passwords and API keys are never written into the repository; they come from the environment of each installation.

## 2.7 Assumptions and dependencies

- A language model with an OpenAI-compatible chat API is available (Gemini by default [11]). Without a key, the rule-based assistant answers, so the shop never depends on the model.
- The demo catalogue (about 220 products with over 1,200 options) is drawn by the project itself until the family photographs the real products; the drawings

use the same sock shapes and colours as the brand.

- Prices, limits, delivery fees and times in the demo are examples; the owners enter the real ones.

## 2.8 User interface plan

The interface was planned as wireframes for the five key screens (catalogue, product with the bag, checkout, the negotiation chat and the administration dashboard) on a phone, a tablet and a laptop before it was built; the final design keeps that structure. Its visual language comes from the stall itself (Section 4.12.2): kraft price tags, the family's handwriting, socks hanging on a washing line, and container 70-E.

# Chapter 3

# User documentation

This chapter explains how to run AK&VEN and how each kind of user works with it: the visitor and the customer in the shop (Section 3.3), and the staff, the owners and the super admin in the administration (Section 3.4). The screenshots show the demo catalogue in English; every screen is also available in Russian and Kyrgyz.

## 3.1 System requirements

### 3.1.1 Server

- Docker with Docker Compose [12] (on macOS, Docker Desktop or Colima; on Linux, Docker Engine);
- about 2 GB of free memory and 3 GB of disk space for the images and the database;
- for the optional language model: an API key of a provider with an OpenAI-compatible chat API (Gemini by default) and outbound internet access.

Without Docker, the backend needs Java 17 and Maven 3.9, the frontend Node.js 22, and the data PostgreSQL 16 with the pgvector extension; the developer documentation (Section 4.13) describes that setup.

### 3.1.2 Client

Any current browser (Chrome, Edge, Safari, Firefox) on a phone, tablet or computer. The shop can be installed as an app from the browser's menu ("Add to Home Screen" or "Install"); once installed it opens in its own window and the bag keeps working without a connection. JavaScript must be enabled.

## 3.2 Installation and start

From the project folder, one command builds and starts the database, the backend and the web server:

```
docker compose up --build
# then open http://localhost:8081 in a browser
```

Code 3.1: Starting the shop

The first build takes a few minutes. The backend has started when its log ends with `Successfully applied 35 migrations`; the database tables are created and, in the demo, filled with the catalogue. To start again from an empty database, run `docker compose down -v` and start again.

### 3.2.1 Demo accounts

| Role | Email | Password |
|---|---|---|
| Super admin | `superadmin@akven.test` | `changeme-super` |
| Owner | `admin@akven.test` | `changeme-admin` |
| Staff | `staff@akven.test` | `changeme-staff` |
| Customer | create one with Sign in, then Create an account | |

Table 3.1: Demo accounts

These accounts exist only in the demo. On a real installation the first super admin is created from the environment, and the demo accounts are switched off at every start.

### 3.2.2 Configuration

Settings are read from environment variables, usually from a file `.env` next to `docker-compose.yml` (an example is in `.env.example`). None of them is required

for the demo.

| Variable | Meaning |
|---|---|
| SUPER_ADMIN_EMAIL, _PASSWORD | The first super admin of a real installation; switches the demo accounts off. |
| DEMO_ACCOUNTS=on | Keeps the demo accounts for a presentation. |
| LLM_API_KEY, LLM_MODEL | Lets a language model answer the chat (Gemini by default). |
| SHOP_CONTACTS | The family's real phone numbers and messengers, kept out of the repository. |
| JWT_SECRET | Optional signing key for logins; without it each installation creates its own. |
| CORS_ALLOWED_ORIGINS | The web addresses allowed to call the API from a browser. |

Table 3.2: The main settings

## 3.3 The shop

### 3.3.1 Everywhere: the header, languages, currencies and the footer

The header holds the shelves (Shop, Men, Women, Kids, Gift Sets, Our Story), the logo, a Wholesale button, and icons for the stall, search, saved socks, the account and the bag. The bar above it switches the currency (US dollars, Kyrgyz som, Russian roubles, converted at the owners' rates), the language (EN, RUS, KYR, the last two written in Cyrillic) and light or dark colours. The whole site, including messages from the server and the assistant's answers, follows the chosen language. On a phone the shelves move into a menu.

The footer (Figure 3.1) answers the last questions a visitor has: whether the stall is open right now (the sign on container 70-E reads open or closed in Bishkek time), the address with links to Google Maps and 2GIS, how pickup, delivery and payment work, every page grouped, the contacts, and a link to the privacy page, which explains in plain words what the shop keeps and why.





Figure 3.1: The footer: the stall's door with its open or closed sign, the promises as sewn labels, every page and the contacts

### 3.3.2 The home page

The home page (Figure 3.2) opens on the socks: a still life of the everyday colours in an AK&VEN box, two buttons and the facts that matter. Below follow the four shelves as washing lines on their own fabrics (Figure 3.3), the newest socks, the price ladder, the fitting room, what families say, a gift box, the family planner, the story of the two names, and a short scene in which container 70-E opens as the visitor scrolls.




Figure 3.2: The home page





Figure 3.3: Shop by who it is for: each shelf on its own fabric, with its socks on the line

### 3.3.3 The shelves: browsing and filtering

A shelf (Figure 3.4) opens on its fabric with its socks pegged on the line and a tag with the number of products. The tabs switch between all socks, men, women, children and gift boxes. The owners' sections are drawn as occasions (Classic, Casual,

Sport, Thermal, Home, Heritage); below them, a bar that stays in reach while scrolling filters by height (no-show to knee-high), by size and by colour, shows only socks in stock and sorts by newest, name or price. Every number on a filter says how many products it would leave; a choice that would leave none is disabled. Each chosen filter appears as a tag that removes it with one tap (Figure 3.5). The list grows twelve at a time with *Show 12 more*, and a thread shows how much of the shelf has been seen. Everything is kept in the address, so a filtered shelf can be bookmarked, shared or reached again with the Back button.





Figure 3.4: The men's shelf





Figure 3.5: Occasions, heights, sizes and colours; the chosen size shown as a tag

On every card the heart saves the sock, and *Quick view* lets the visitor choose a colour and a size and add it to the bag without leaving the shelf.

### 3.3.4 A product

The product page (Figure 3.6) shows the pictures (the picture follows the chosen colour), the name, the price, the colours and sizes, the honest stock (in stock, only a few left, arriving in about $n$ days, or sold out with *Tell me when it's back*), the quantity and *Add to bag*. Under them come when the order can be collected, the delivery countries and the collection discount, then *How the price falls* (Figure 3.7): a slider of pairs that shows the price of one pair and of all of them as the pairs add up, with the shop's price steps marked. Further down are the size finder, fabric, quality and care, the same design for the rest of the family, reviews and *Complete the set*. When the buy button scrolls out of view, a small bar with the picture, the price and *Add to bag* stays at the bottom of the screen.





Figure 3.6: A product page





Figure 3.7: How the price falls: the price per pair and in total as the number of pairs grows

### 3.3.5 Asking for a better price

A signed-in customer can ask for a better price in the chat on the product page (Figure 3.8), in any of the three languages, in their own words: “Can you give me 50% off for 10 pairs?”. The assistant answers as the stall would, remembers the

conversation, answers questions about the sock, and shows an offer with the old and the new price. The offer can be put into the bag with one tap. The rules of an offer are shown with it:

- it never goes below the owners' limit for that sock, whatever was asked;
- it is valid for 24 hours, for at least the number of pairs it was made for, and can be used once;
- at checkout, the better of the offer and the collection discount applies, never both.

A customer can send twenty messages in ten minutes; after that the chat asks them to wait a little.





Figure 3.8: The chat: asked for 50%, the assistant offers what the owners allow

### 3.3.6 The fitting room, the size guide and the sock finder

The fitting room (Figure 3.9) draws the shop's own socks on a leg: the visitor chooses who is trying on, the shoes (sneakers, dress shoes, loafers, boots or at home) and a height; each height is rated for those shoes with a reason, the shoe size gives the sock size, and the trousers can be set to the visitor's colour (*Match my trousers* finds socks that go with them). The size guide gives the sizes each customer knows (EU and US in English, local sizes in Russian and Kyrgyz) and how to measure a

foot. The sock finder asks who, how high and what for in three taps and shows the matching socks.





Figure 3.9: The fitting room

### 3.3.7 The family planner and gift boxes

In the family planner on the home page (Figure 3.10) a customer adds each person and their shoe size and the number of pairs. The sock size comes from the size chart, and the price step reached by the whole set is shown. The list can be taken to the shop with these sizes or sent to the family in a message. Signed in, the family (names, sizes, birthdays) is kept in the account; product pages then say who in the family a shelf fits, and a birthday within a month suggests a gift box.





Figure 3.10: The family planner, kept on a sheet of paper pegged to the page

A gift box (Figure 3.11) is built in three steps: a kraft, navy or red box with a ribbon, a hand-written card, and socks from any shelf. The drawing shows the socks in the box and the lid closing over them; the family packs it at the stall, and the order tells them how.





Figure 3.11: Building a gift box

### 3.3.8 The bag, checkout and payment

The bag (Figure 3.12) counts all its pairs as one collection: it shows the minimum order, the step reached and how many more pairs reach the next one. Prices are always taken from the server; if a price or the stock changed since the sock was added, the bag says so. A line can be removed or saved for later, which moves it to the saved socks.





Figure 3.12: The bag as one collection

Checkout (Figure 3.13) needs no account: a guest gives an email address, where the confirmation and a private link to the order go; signing in adds saved details, agreed prices and the list of orders. It asks for a name and a phone number and how to receive the order: pickup at container 70-E, a courier in Bishkek and the Chui region, or cargo to the regions, Kazakhstan, Uzbekistan or Russia. Each area or carrier shows its fee, the days it takes, from which amount delivery is free and the owners' note; a carrier paid on receipt says so, and the summary says how much more makes delivery free. *Remember my details* keeps the name, phone, area and address for next time. Payment is with Apple Pay or Google Pay (Figure 3.14); the wallet in this thesis is simulated and the dialog says so, and it can be told to decline in order to show what happens then: nothing is charged and the bag stays.





Figure 3.13: Checkout with a delivery area





Figure 3.14: The simulated wallet

### 3.3.9 Orders and pickup

A paid order (Figure 3.15) shows its timeline (placed, paid, ready or on its way, delivered), the socks, the delivery area and time, and for pickup a six-digit code and a QR code. At the stall the customer says the code and the last four digits of their phone number. A paid order can be cancelled until it is handed over; the payment is refunded and the socks go back on the shelf. *Order these again* fills the bag with

the same socks. Each step is also emailed in the customer's language. A guest's order lives at its private link; *Find my order* emails a lost link again, given the email address and the order number.





Figure 3.15: A paid order

### 3.3.10 The account

The account (Figure 3.16) holds the family, the saved contact and delivery details (to change or forget), the sold-out options the customer waits for, and the recent orders. Saved socks (the heart) are kept in the browser and, once signed in, with the account; the list can be shared as a link. Socks the customer looked at last appear as a row of pegged photos under the shelves and on product pages, and can be cleared.





Figure 3.16: The account

### 3.3.11 Wholesale and company gifts

The wholesale page (Figure 3.17) is for shops, market stalls, teams and companies. It explains who orders, how a case is made, and the facts a buyer needs (packs of 10 to 12, about 240 pairs to a case, the four countries). In *Build a case* (Figure 3.18) the buyer chooses dozens from each shelf and watches the case fill; the mix goes into the request. The request (Figure 3.19) needs the name of the shop, a city and a way to answer (WhatsApp, Telegram, a call or e-mail). It is kept by the shop and answered with a reference number such as W-5018A33E, and the same text can be sent to the family's messenger. Wholesale prices are not published, because they follow the dollar rate, the factory price and the delivery; the family answers with a price.





Figure 3.17: The wholesale page





Figure 3.18: Building a case





Figure 3.19: A request sent, with its reference

### 3.3.12 Finding the stall

*Find us at Dordoi* (Figure 3.20) tells whether the stall is open now, the week's hours, the address step by step inside the bazaar, and links to Google Maps and 2GIS. The address can be copied in one tap.





Figure 3.20: Find us at Dordoi

### 3.3.13 On a phone

Every page is laid out for phones, tablets and laptops. Figure 3.21 shows the home page and the children's shelf on a phone in Kyrgyz.





Figure 3.21: The home page and the children's shelf on a phone, in Kyrgyz

## 3.4 The administration

The administration is opened at `/admin` by a staff, owner or super admin account. Its menu (on the left) groups the screens by who may use them: *Shop* for everyone in the team, *Owners* for the owners and *System* for the super admin. The language can be switched at the bottom of the menu.

### 3.4.1 For the whole team

**Products.** The list (Figure 3.22) can be searched and filtered (in the shop, removed). One screen (Figure 3.23) adds or edits a product: name, audience, section, cut,

description, fabric, quality, care and origin; its options (colour with swatch, size, pack, price, stock, stock on the way and when it arrives); and its pictures, each of which can belong to one colour. Pictures are uploaded as JPEG, PNG or WebP of up to 5 MB. Removing a product hides it from the shop; it can be restored. Every change appears in the product's history.





Figure 3.22: Products





Figure 3.23: Adding a product

**Orders and hand-over.** *Orders* (Figure 3.24) lists the orders by status; a gift order says how to pack it, a delivery order the area and the fee. An order can be marked as handed over or cancelled (with a refund). *Hand over an order* (Figure 3.25) is the stall's screen: the customer's code, typed or scanned from their QR code, and the last four digits of their phone number.





Figure 3.24: Orders





Figure 3.25: Handing an order over at the stall

**Sections and cuts** are the owners' own groups of the catalogue; they can be added, renamed, hidden, reordered, and deleted when no product uses them.

**Negotiations and the dashboard.** *Negotiations* (Figure 3.26) lists every conversation with what the assistant proposed and what was allowed. The dashboard (Figure 3.27) shows paid orders, revenue and pairs sold per day, orders waiting at the stall, socks running out with what is on the way, customers waiting for a sold-out option, and for the assistant the offers per day, how often the limit stepped in and how many offers became orders.





Figure 3.26: Negotiations: proposed and allowed, side by side





Figure 3.27: The dashboard

**Reviews and wholesale requests.** Reviews wait for approval before they are shown. *Wholesale requests* (Figure 3.28) is the inbox of requests from shops and companies, newest first: the reference, the company, the city, the pairs and the mix, the contact with a *Reply* button that opens the customer's own WhatsApp, Telegram, phone or e-mail, a note for the family, and the status (new, in progress, answered, closed).





Figure 3.28: The inbox of wholesale requests

### 3.4.2 For the owners

**Pricing** (Figure 3.29) sets the minimum order, the ladder of discounts by pairs, and the som and rouble rates with their rounding. The limit of each sock (how much it may be discounted at most) and its cost price are set on the product's options and are visible only to the owners.





Figure 3.29: Pricing

**Delivery areas** (Figure 3.30) are where the shop delivers: for each area the country, a name, whether it is a courier area or a cargo carrier, the fee in US dollars, the amount from which delivery is free, the shortest and longest time in days, a note for customers, and for a carrier whether the customer pays it on receipt. An area can be hidden from checkout or deleted; orders that used it keep their copy.

**Emails to customers** lists every email the shop wrote: to whom, about what, in which language, whether it went out, and the email itself; the order's page shows its own. Without a mail server the page says that the emails are kept and not sent, and *Send again* delivers one once a server is set up.





Figure 3.30: Delivery areas

**Customers, contacts and the stall, and the size chart.** The owners can mark trusted customers, give a customer a new password or switch a fake account off; enter the contacts shown in the shop and the stall's address and opening hours; and edit the size chart from which the shop derives every sock size.

### 3.4.3 For the super admin

*Accounts* adds staff and owner accounts, changes their role, disables them or sets a new password; a disabled account or a new password ends its sessions at once. *AI assistant* (Figure 3.31) chooses who answers the chat (the language model or the rules), shows whether a key is set (never the key itself), offers a box to try a message, and repeats the evaluation of Section 5.5 against the live model. The *Audit log* (Figure 3.32) shows every change with who made it and the values before and after.





Figure 3.31: Choosing and trying the assistant





Figure 3.32: The audit log

## 3.5 Troubleshooting

**The page shows an older version.** Reload without the cache (Ctrl+Shift+R, or Cmd+Shift+R on a Mac); an installed app updates on its next start.

**"Too many attempts" at sign-in.** After five wrong passwords for an account

from one address, sign-in waits for fifteen minutes; the message says how long.

**The chat says to wait a little.** A customer can send twenty messages in ten minutes.

**The assistant answers but the language model is not used.** Without `LLM_API_KEY`, or when the model does not answer in time, the rules answer; the super admin sees which one answered under AI assistant.

**A delivery country is missing at checkout.** The country has no area shown at checkout; the owners add one under Delivery areas.

**The backend does not start.** Check that port 8080 and 5432 are free and that Docker has enough memory; the backend log names the reason.

## 3.6 Limitations

Payment is simulated: no money moves and the wallet does not contact Apple or Google. The shop sends no e-mails or SMS; customers follow their orders in the account. Product pictures are drawings until the family photographs the real socks. The section and colour names come from the owners' data and are shown as entered, in one language.

# Chapter 4

# Developer documentation

This chapter describes how AK&VEN is built: the overall design and the reasons for it, the technologies, the backend packages, the data model, the API, security, the pricing and negotiation logic, the remaining domain features, the frontend, and how the system is built and deployed. Testing and evaluation follow in Chapter 5.

## 4.1 Overview

The system has three layers (Figure 4.1):

1. **Client:** one progressive web application in React and TypeScript. The shop and the administration are the same application with role-gated routes, not two programs.

2. **API:** one Spring Boot service that holds all business rules: catalogue, pricing, negotiation, orders, payment through a wallet interface, accounts and the audit log. The browser never decides a price.

3. **Data:** PostgreSQL 16 with the pgvector extension. The schema is created and changed only by versioned Flyway migrations [13]; Hibernate validates it at start and never alters it.





Figure 4.1: Architecture overview

The shape is deliberately modest. Open-source platforms such as Shopizer, Medusa and Saleor (Section 1.2) solve many shops on many servers; this project serves one family stall with a few thousand options, so one service and one database are enough, and every additional moving part (a message broker, a separate vector store, microservices) would add operational cost without benefit. What the platforms contributed is the idea that the administration is only another client of the same API with more rights.

## 4.2 Technology stack

| Part | Technology and reason |
|---|---|
| Backend | Java 17, Spring Boot 3.5 [14], Spring Security [15], Spring Data JPA with Hibernate 6, Bean Validation. A mature, strongly typed stack with declarative transactions and method security. |
| Database | PostgreSQL 16 [16] with pgvector; Flyway migrations. Check constraints, generated columns and partial indexes let the database repeat the business rules. |
| API style | REST with JSON; errors as RFC 7807 problem details [17]; JWT bearer tokens [18]; OpenAPI documentation generated at `/swagger-ui`. |
| Frontend | React 18 [19], TypeScript [20], Vite [21], React Router; no UI framework: the design system is written in CSS for the brand. A service worker and a web app manifest make it a PWA. |
| Assistant | A `Negotiator` interface with a rule-based implementation and a language-model implementation over any OpenAI-compatible chat API (Gemini by default [11]). |
| Tests | JUnit 5 [22], MockMvc, JaCoCo [23]; Vitest [24] and Testing Library; Playwright [25] with axe-core [26] for the browser journey. |
| Delivery | Docker Compose [12] (database, backend, nginx web server); CI on GitHub Actions and on the ELTE GitLab. |

Table 4.1: Technology stack

## 4.3 Repository orientation

```
backend/ Spring Boot application
  src/main/java/com/akven/thesis/
     audit auth catalog common config delivery family media negotiation
     order payment pricing review saved settings shop sizes stock user wholesale
  src/main/resources/db/migration schema migrations (always applied)
  src/main/resources/db/seed demo data (demo profile only)
frontend/ the shop and the administration (React + TypeScript)
  src/api auth cart brand components pages admin shop i18n styles test
  scripts/ product pictures, logo, icons, screenshots, end-to-end test
docs/ requirements, architecture, diagrams, this thesis
docker-compose.yml .github/workflows/ci.yml .gitlab-ci.yml
```

Code 4.1: Repository layout

The backend has about 10,800 lines of Java in 21 packages, organised by business feature rather than by technical layer: each package holds its entity, repository, service, controller and data-transfer records. The frontend has about 17,200 lines of

TypeScript and CSS. Tests add about 5,300 lines on the backend and 1,500 on the frontend, plus the browser journey.

## 4.4 System design

### 4.4.1 Layers inside the backend

Each request passes through the same layers:

**Filters.** A correlation-id filter gives every request an id that appears in the logs and in audit entries; the JWT filter authenticates the caller from the token and reads the account from the database on every request.

**Controllers.** Thin REST controllers that validate the request body (Bean Validation) and pass the caller's email, taken from the token and never from the body, to a service.

**Services.** All business rules, in transactions; owner-only and staff rules are enforced here with `@PreAuthorize`, so they hold for every caller and not only for one URL.

**Repositories and entities.** Spring Data repositories; entities protect their own state transitions (an order cannot skip from pending to handed over).

Errors are one format: a business-rule exception becomes 400, a missing record 404, a conflict or a lost optimistic-lock race 409, a rate limit 429 with `Retry-After`, and a declined payment 402, all as problem details whose text the frontend shows to the user.

### 4.4.2 Roles

There are four roles: `CUSTOMER`, `STAFF`, `ADMIN` (the owners) and `SUPER_ADMIN`. A Spring role hierarchy makes `SUPER_ADMIN` include `ADMIN`, so owner rules need not mention the super admin. URL rules give the public catalogue, sign-in, registration, the price quote, the shop's information, delivery areas, wholesale requests, checkout and a guest's own order (which the service opens only with its private link) to everyone, `/api/admin/**` to the team, and everything else to signed-in users; method security refines this inside the services.

## 4.5 Data model

Figure 4.2 shows the core tables; the full schema of 35 Flyway versions (19 schema migrations and 16 demo-data migrations) is generated from the database into the `docs/diagrams` folder.





*Figure 4b. Core data model: 7 of 10 tables, key columns.*

Figure 4.2: The core of the data model

| Table | Purpose |
|---|---|
| product, variant | A sock style and its sellable options (size, colour, pack, price, stock, reserved stock, cost price and limit). Products are removed softly so old orders stay intact. |
| catalog_term | The owners' sections and cuts. |
| product_image | Ordered pictures, each optionally tied to one colour. |
| customer_order, order_item | Orders with their status, payment reference, pickup code, gift packing and delivery copy; lines keep a snapshot of the name, picture and price paid and which rule set it. |
| negotiation_session, negotiation_turn | A conversation about one option and every message of it, with the proposed and allowed discount and the assistant that answered. |
| price_tier, shop_policy | The ladder of discounts by pairs, the minimum order, exchange rates. |
| delivery_zone | Delivery areas: courier or cargo carrier, fee, free-from amount, days, a note, and whether the carrier is paid on receipt. |
| outbound_email | The outbox: every email to a customer, its language, state and attempts. |
| wholesale_request | Requests from shops and companies with their status. |
| customer_details | Contact and delivery details a customer asked to keep. |
| family_member, saved_item, product_review, stock_request | Family profiles, saved socks, reviews and waiting for sold-out options. |
| app_user, app_setting | Accounts with role and state; small run-time settings. |
| shop_contact, pickup_point, size_chart_row | The shop's contacts, the stall with its hours, and the size chart. |
| audit_log_entry | Who changed what, with the state before and after as JSON. |
| product_embedding | Prepared for vector retrieval (pgvector); not used yet. |

Table 4.2: The main tables

### 4.5.1 Integrity in the database

Several rules are enforced by the database as well as by the code, so that a bug in the service layer cannot write an impossible row:

- `available_qty` is a generated column (`stock_qty - reserved_qty`) and `CHECK (stock_qty >= reserved_qty)` keeps stock from going below what is reserved.
- `CHECK (validated_discount_pct <= proposed_discount_pct)` on negotiations: the allowed discount can never exceed the proposal.
- A paid order must have a payment reference; a delivery order must have an address; a negotiated offer can be used by one order line only (a unique index).
- Optimistic locking (a `version` column) on accounts, products, variants and orders turns a lost-update race into an error instead of a silent overwrite [27].
- Delivery fees, review ratings, wholesale quantities, contact kinds and statuses are checked by `CHECK` constraints; e-mail addresses are unique regardless of case.

An order keeps a copy of everything that may change later (the product name and picture, the price paid, the delivery area's name, fee and days), so editing or deleting a product or a delivery area never changes an old receipt.

## 4.6 REST API

The API has 107 endpoints. Table 4.3 groups them; the full list with request and response shapes is generated at `/swagger-ui/index.html`.

| Endpoints | Purpose |
|---|---|
| *Public* | |
| `GET /api/products`, `/facets` | Catalogue with filters and live counts per section, cut, size, colour. |
| `GET /api/products/{slug}` | A product with options and pictures, never cost or limit. |

| Endpoints | Purpose |
|---|---|
| `POST /api/cart/quote` | Prices a bag: lines, collection step, minimum, next step. |
| `GET /api/pricing`, `/api/sizes` | Public price ladder; size chart and size finder. |
| `GET /api/shop/info`, `/delivery-zones` | Contacts, the stall, opening hours; delivery areas. |
| `POST /api/wholesale/requests` | A wholesale or company request (rate-limited). |
| `POST /api/auth/register`, `/login` | Accounts and tokens (rate-limited). |
| *Signed-in customer* | |
| `POST /api/negotiate` | One message of a negotiation. |
| `POST /api/orders`, `GET /api/orders` | Checkout (with `Idempotency-Key`); own orders; cancel. |
| `/api/family`, `/api/saved`, `/api/account/details` | Family, saved socks, kept details. |
| `/api/reviews`, `/api/stock-requests` | Own review; waiting for sold-out options. |
| *Team (staff and above)* | |
| `/api/admin/products`, `/variants`, `/terms` | Catalogue, options, pictures, sections and cuts. |
| `/api/admin/orders`, `/handover` | Orders, hand-over with code, fulfil, cancel. |
| `/api/admin/negotiations`, `/summary` | Transcripts, statistics, the dashboard. |
| `/api/admin/reviews`, `/wholesale` | Moderation; the wholesale inbox. |
| *Owners* | |
| `/api/admin/pricing`, `/delivery-zones` | Ladder, minimum, rates; delivery areas. |
| `/api/admin/customers`, `/shop`, `/sizes` | Customer accounts, contacts and stall, size chart. |

| Endpoints | Purpose |
|---|---|
| *Super admin* | |
| `/api/admin/accounts`, `/assistant`, `/audit` | Team accounts, assistant switch and evaluation, audit log. |

Table 4.3: The API by audience

## 4.7 Security

- **Passwords** are hashed with BCrypt; a password is limited to 72 characters, the length BCrypt reads, so a longer one is refused rather than silently cut.
- **Tokens.** Each installation signs its tokens with its own random 384-bit key unless one is configured; no key is in the repository. The JWT filter reads the account on every request, so a disabled account or a new password ends its sessions at once, and the role comes from the database, not from the token.
- **Brute force and abuse.** Five failed sign-ins per account and address lock that pair for fifteen minutes; sign-ups, chat messages and wholesale requests are rate-limited in sliding windows. The limiters forget old entries once they hold many, so a flood of different addresses cannot grow memory without end.
- **The visitor's address** is taken from `X-Forwarded-For` only when the request comes through a proxy on a private network, so limits count visitors and not the web server.
- **Input.** Every request body is validated; free text (reviews, gift cards, wholesale notes, saved details) is stored as plain text with control characters removed and is rendered by React as text, never as markup. The orders spreadsheet is protected against CSV injection [28]. Uploaded pictures are accepted by their content, not their name, with random stored names; SVG is refused.
- **Secrets and private data.** Cost prices and limits never appear in customer responses (explicit DTOs, asserted by tests). The language model's key is read from the environment and never stored, shown or logged; real phone numbers come from the environment.

- **Headers.** The API sends a strict Content-Security-Policy, `no-referrer` and a permissions policy; the web server sends a CSP that allows only the site's own scripts, `nosniff` and `frame-ancestors 'none'`. CORS allows only configured origins, without credentials.
- **Audit.** Every change by the team is written to the audit log in the same transaction (the audit service requires an existing transaction), with the correlation id of the request.

## 4.8 Pricing and the PolicyValidator

### 4.8.1 Collection pricing

A bag is priced as one collection. The owners set a minimum number of pairs and a ladder of steps, for example 3% off every pair from 20 pairs, 5% from 30, 8% from 50 and 10% from 100. Packs count with their number of pairs. The `CollectionPricing` component counts the pairs of the whole bag, finds the step reached and the next one, and the quote tells the customer how many more pairs reach it. The quote is public and is recomputed on every change; the browser only shows it.

### 4.8.2 The validator

Every discount, whether it comes from the ladder or from a negotiation, passes through one method before it can touch a price (Code 4.2). Each option has a limit (`marginFloorPct`) set by the owners: the largest discount it may ever get. The method is deliberately trivial: it is easy to test exhaustively, it does not depend on the model, and it cannot be talked into anything.

```
1
2  /**
3   * The safety gate described in the architecture doc: the ONLY code allowed to
4   * turn a proposed discount into something that can touch an order. Deliberately
5   * plain, deterministic, and independent of the LLM call -- treat whatever the
6   * negotiation service hands in as untrusted input, the same way you'd never
7   * trust a client-submitted price.
8   */
9  @Component
10 public class PolicyValidator {
```

```

    /**
     * @param proposedDiscountPct what the LLM suggested -- never trusted
         directly.
     * @param variant the SKU being negotiated, whose marginFloorPct is the hard
         limit.
     * @return the discount actually allowed: min(proposed, marginFloorPct),
         never negative.
     */
    public BigDecimal clamp(BigDecimal proposedDiscountPct, Variant variant) {
        if (proposedDiscountPct == null || proposedDiscountPct.signum() < 0) {
            return BigDecimal.ZERO;
        }
        return proposedDiscountPct.min(variant.getMarginFloorPct());
    }
}
```

Code 4.2: The PolicyValidator

At checkout, `PricingService` decides the price of each line (Code 4.3): the better of the negotiated offer and the collection step is chosen, never both, and the result passes through the validator again. A negotiated offer is accepted only if it belongs to the same customer and option, has not expired (24 hours), is used for at least the negotiated number of pairs, and has not been used before; the line records which rule set its price and whether the limit stepped in.

```
    private PricedLine decide(Variant variant, BigDecimal tier, BigDecimal
        negotiated, UUID sessionId) {
        BigDecimal list = variant.getPrice();
        boolean offerWins = negotiated.compareTo(tier) > 0;
        BigDecimal wanted = offerWins ? negotiated : tier;
        BigDecimal pct = policyValidator.clamp(wanted, variant);
        DiscountSource source = pct.signum() == 0 ? DiscountSource.NONE :
            offerWins ? DiscountSource.NEGOTIATED : DiscountSource.TIER;
        BigDecimal unit = list.multiply(BigDecimal.valueOf(100).subtract(pct)).
            divide(BigDecimal.valueOf(100), 2, RoundingMode.HALF_UP);
        // The offer stays linked even when the tier was better: it was presented
            at checkout and is used up with this order.
        return new PricedLine(list, pct, unit, sessionId, tier, source, pct.
            compareTo(wanted) < 0);
    }
```

Code 4.3: Deciding the price of an order line





Figure 4.3: The validation path: the proposal is untrusted until the validator has clamped it

## 4.9 The negotiation assistant

### 4.9.1 Design

`NegotiationService` handles one message (Figure 4.4). It builds a `NegotiationContext` with the product, its price, the quantity, the public

price ladder, the stock status, the conversation so far and the customer's message; by construction the context has no field for the cost price or the limit, so they cannot reach the model. It asks a `Negotiator` for a proposal (a discount and a reply), clamps the discount with the validator, stores the turn with both numbers, and fills the reply's placeholders with the allowed numbers.





Figure 4.4: One negotiation turn

There are two negotiators behind the same interface:

- `RuleBasedNegotiator` answers instantly from rules about quantity and reasons; it is deliberately willing to over-promise, so that tests show the validator

stepping in.

- `LlmNegotiator` calls a language model through `OpenAiCompatibleChatClient`. It is wrapped by `FallbackNegotiator`, which answers with the rules if the model fails, is slow or returns something unusable; `SwitchingNegotiator` lets the super admin choose at run time.

### 4.9.2 Defences of the language-model negotiator

1. **No secrets in the prompt.** The model never sees the limit or the cost; it can only propose.

2. **Grounding.** `ProductKnowledge` selects the product facts relevant to the question (fabric, care, origin, pack, size); the prompt tells the model to answer only from them and to say it will ask the family otherwise.

3. **The message is data.** The customer's text is fenced in `<customer_message>` tags and the system prompt says it is data, not instructions; claims to be the owner or a developer are to be ignored.

4. **Structured output.** The model must answer with a JSON object of a discount and a reply; anything else is a failure that falls back to the rules.

5. **No numbers in its words.** The reply may not contain any number, price or percentage in digits or words in English, Russian or Kyrgyz (Code 4.4); it writes `{pct}` and `{price}` and the shop fills in the *allowed* numbers. A reply that states a number of its own is replaced by a template.

6. **Clamp and record.** The discount is clamped and both numbers are stored; the database refuses a turn in which the allowed discount exceeds the proposal.

```
1  /**
2   * A reply is safe when, apart from the shop's placeholders, it states no
        number, price or percentage, in digits or
3   * words, in English, Russian or Kyrgyz. The one exception is the customer's
        own quantity ("6 pairs", "six pairs",
4   * "\u043f\u044f\u0442\u044c \u043f\u0430\u0440", "\u0431\u0435\u0448 \u0436\
        u0443\u043f"), which is just repeating the question.
5   */
```

```
6   static boolean isSafe(String reply, int quantity, String language) {
7       if (reply.isBlank()) return false;
8       String lang = Replies.language(language);
9       String stripped = reply.replace("{pct}%", " ").replace("{pct}", " ").
            replace("{price}", " ").toLowerCase(Locale.ROOT);
10      if (quantity >= 1 && quantity < WORDS_EN.length) stripped = stripped.
            replaceAll("\\b" + WORDS_EN[quantity] + "\\b(?=\\s+pairs?\\b)", " ");
11      // The customer's own quantity in digits ("30 pairs", "30 \u043f\u0430\
            u0440", "30 \u0436\u0443\u043f") is only repeating the question too.
12      if (quantity >= 1) stripped = Pattern.compile("(?<![\\d.,])" + quantity +
            "(?=\\s+(pairs?\\b|\u043f\u0430\u0440|\u0436\u0443\u043f))", Pattern.
            UNICODE_CASE).matcher(stripped).replaceAll(" ");
13      if (quantity >= 2 && quantity < WORDS_RU.length) {
14          stripped = Pattern.compile("(?<!\\p{L})(" + WORDS_RU[quantity] + ")
                (?=\\s+\u043f\u0430\u0440)", Pattern.UNICODE_CASE).matcher(
                stripped).replaceAll(" ");
15          stripped = Pattern.compile("(?<!\\p{L})(" + WORDS_KY[quantity] + ")
                (?=\\s+\u0436\u0443\u043f)", Pattern.UNICODE_CASE).matcher(
                stripped).replaceAll(" ");
16      }
17      if (NUMBERISH_EN.matcher(stripped).find() || stripped.contains("{") ||
            stripped.contains("}")) return false;
18      if ((lang.equals(Replies.RU) || lang.equals(Replies.KY)) && NUMBERISH_RU.
            matcher(stripped).find()) return false;
19      return !(lang.equals(Replies.KY) && NUMBERISH_KY.matcher(stripped).find())
            ;
20  }
```

Code 4.4: A reply may state no number of its own (Cyrillic shown as Java Unicode escapes)

## 4.10 Orders, stock and payment

Checkout (`OrderService`) is the place where races matter: two customers may buy the last pair at the same moment, and a double click must not charge twice. The method therefore:

1. returns the earlier order when the same `Idempotency-Key` is seen again from the same customer (a unique index backs this);

2. locks the variants in the bag with `SELECT ... FOR UPDATE` in SKU order before looking at the stock, so two carts in opposite orders cannot deadlock and the last pair goes to one buyer;

3. prices every line on the server and reserves the stock;

4. adds the delivery fee of the chosen area (zero above its free-from amount) to the total;

5. charges the wallet through the `PaymentProvider` interface with only a token; a decline or an outage cancels the order and releases the stock, and that outcome is committed;

6. marks the order paid with the provider's reference, gives a pickup code, and audits each step.

The order's status machine lives in the entity: pending, paid, fulfilled, or cancelled from pending or paid (with a refund and the stock returned). The simulated wallet accepts only token shapes of Apple Pay and Google Pay and refuses anything that looks like a card number.

## 4.11 Further domain features

**Delivery areas.** `DeliveryService` answers which area an order travels in: the chosen active area, or the first active area of the country. Owners edit areas with checks that the longest time is not shorter than the shortest and that a free area has no free-from amount; every change is audited. A fresh installation starts with one free area per country, so delivery works as before until the owners set prices.

**Courier and cargo.** An area is a *courier* area (Bishkek and the Chui region, where the family calls a taxi or brings a large order in its own car, free above the area's amount) or a *cargo carrier* (the bus cargo to Osh, carriers to Kazakhstan, Uzbekistan and Russia), which can be paid by the customer on receipt. The order keeps its own copy of the kind and the payment on receipt, like the fee, so the receipt never changes.

**Emails through an outbox.** `Notifier` writes each email to a customer (confirmed, handed over, cancelled; a wholesale request received) into `outbound_email` *inside the transaction that changes the order*, in the language the customer used at checkout. A change that rolls back therefore sends nothing, and a mail server that is down loses nothing: `EmailSender` delivers the queue every few seconds through any SMTP server, tries a refusal again after 1, 2, 4 and 8 minutes and then marks it failed. Without a mail server nothing leaves the shop and each email is marked *not sent* but stays readable in the admin. Emails hold names and addresses, so they are deleted after 90 days. The texts live in three property files, and a test fails when a sentence is missing in one language. The acknowledgement of a wholesale request carries only its reference and number of pairs, never text the visitor typed, so the public form cannot be used to send someone's words to a stranger.

**Checkout without an account.** An order has either an account or a guest's email (a database check keeps exactly one). A guest opens the order at `/orders/<id>#t=<key>`. The key is an HMAC-SHA256 of the order id under a key derived from the installation's secret, so nothing is stored, a retried checkout returns the same link, and the key can never pass as a login token. It stands after the `#`, which browsers never send, so it reaches no access log; the page sends it in an `X-Order-Token` header and the server compares it in constant time. A guest who lost the link gives the email and the order number, and the link is emailed to the order's own address; the answer is the same whether anything matched, so the form reveals no customer. Guest checkouts and link requests are limited per address. Negotiated prices still need an account, because an offer belongs to the account that negotiated it; and guest orders are never joined to an account by email, because an email address is not proof of identity.

**Wholesale requests.** `WholesaleService` accepts requests without an account. The contact is checked against its kind (a phone number for WhatsApp and calls, a Telegram name or number, an e-mail address); text is cleaned; a hidden trap field, which people never see, makes a bot's request look accepted while nothing is kept; and a sliding window allows five requests per address and sixty for the whole shop per hour. The team moves a request through new, in progress, answered and closed; a picked-up request cannot become new again; every change is audited.

**Saved details, family and reviews.** Each customer reads and writes only their own family, saved socks and kept details: the services take the account from the token, never an id from the request. Reviews are accepted only from customers whose order with that sock was handed over, are shown only after approval and never show an e-mail address.

**Catalogue facets.** The filter counts are computed with criteria queries under the same specification as the list, each dimension ignoring its own selection, so the alternatives keep their counts. Sizes and colours count only options that are for sale (and in stock, or of the chosen colour or size, when those are chosen), so "M" means a product that can be bought in M.

## 4.12 Frontend

### 4.12.1 Structure

The application starts in `main.tsx`; `App.tsx` declares the routes. Rarely used screens (the administration, checkout, orders, the style guide) are loaded on demand, which keeps the shop's first script small.

**`api/`** a typed client that adds the token, turns problem details into readable errors with field messages, and one function per endpoint;

**`auth/`, `cart/`** the session (kept in `sessionStorage`) and the bag (in `localStorage`, validated field by field when read, shared across tabs);

**`pages/`, `admin/`** the shop's and the administration's screens;

**`shop/`** features shared by several pages: the family, saved and recently viewed socks, the fitting room, the home page's sections, the wholesale case builder;

**`brand/`** the logo and the sock drawing, shared with the script that draws the product pictures;

**`i18n/`** all texts in English, Russian and Kyrgyz (about 1,600 keys per language) with typed keys, so a missing translation is a compile error, and plural rules through `Intl.PluralRules`;

**`styles/`** design tokens for the light and dark themes and the components.

### 4.12.2 Design system

The visual language comes from the stall: kraft price tags on strings, the family's handwriting (Caveat) beside a Garamond serif (Cormorant Garamond) and a clear sans-serif (Onest), navy and gold from the logo. Instead of plain boxes, the interface uses objects of the stall: socks pegged on a washing line (a `Clothesline` component that hangs drawn socks by the cuff and lets them swing from the peg), shelves on knitted, ribbed, spotted and wrapping-paper fabrics, contacts as paper tags, the promises in the footer as sewn-in labels, forms as sheets of paper pegged up, and the stall's door with an open or closed sign in Bishkek time. All product pictures are drawn by a script from the same sock shapes the interface uses, hanging on the line, so the shop looks consistent until real photographs replace them.

Motion follows two rules that keep it smooth on cheap phones: only `transform` and `opacity` are animated, and nothing that changes the layout runs while scrolling. Every animation stops for visitors who prefer reduced motion. Colour contrast is checked by a test against WCAG 2.2 AA [29] for every pair of text and background tokens in both themes.

### 4.12.3 State and data flow

Server data is loaded with a small `useAsync` hook that cancels requests that are no longer needed; shared client state (the bag, the session, saved socks, recently viewed, the family) lives in small stores read with `useSyncExternalStore`, so several components stay in step without a state library. Filters live in the address bar, which makes every view shareable and the Back button meaningful.

## 4.13 Running and building

**With Docker.** `docker compose up -build` starts three services: `db` (PostgreSQL 16 with pgvector), `backend` (the Spring Boot jar, demo profile) and `web` (nginx serving the built frontend and passing `/api` to the backend), with volumes for the data and uploaded pictures.

**Without Docker.** Start PostgreSQL with the vector extension, then the backend with `mvn spring-boot:run` (profile `demo` for the catalogue) and the frontend with

`npm run dev`; Vite passes `/api` to the backend. `npm run art` draws the product pictures again.

**Continuous integration.** Every push runs six jobs on GitHub Actions, and the same checks on the ELTE GitLab: the backend tests with the coverage gate, the tests on real PostgreSQL, a smoke test of the jar against PostgreSQL, the frontend type check, tests and build, the browser journey against the real stack, and a Docker Compose smoke test that starts the whole system and checks the security headers.

## 4.14 Design trade-offs and known limitations

- **Payment inside the checkout transaction.** With the simulated wallet the charge is instant; a real provider would move outside the transaction (reserve, pay, confirm, with a timeout releasing the reservation).
- **Rate limits in memory.** Right for one backend; several would share them through the database or Redis.
- **Keyword retrieval.** The assistant's facts are selected by keywords; the vector table is prepared for embedding-based retrieval.
- **Offline.** The bag works offline; product pages are not cached, and orders need a connection.

# Chapter 5

# Testing and evaluation

## 5.1 Testing strategy

The tests are arranged by what they can prove:

**Unit tests** prove small rules exactly: the validator, the collection ladder, the limiters, the contact checks, the reply filter of the assistant.

**Integration tests** run the whole Spring application against an in-memory database through the real security filters (MockMvc) and prove each feature end to end at the API: who may do what, what is stored, what is audited.

**Database tests** run on a real PostgreSQL 16, because some properties exist only there: migrations, check constraints, generated columns, row locks and the 401/403 behaviour of a real servlet container.

**Frontend tests** render components with a fake server and check what the user sees and what is sent.

**The browser journey** starts the real backend and frontend and walks through the owner's, the customer's and the super admin's work in a real browser, with accessibility rules checked on every page.

Table 5.1 summarises the suites as they stand at the end of the project.

| Suite | Command | Result |
|---|---|---|
| Backend | `mvn verify` | 257 tests, 97% line coverage; the build fails below 80% |
| Real PostgreSQL | `-Dtest=PostgresIntegrationTest` | 11 tests over real HTTP on PostgreSQL 16 |
| Frontend | `npm test` | 204 tests, type check and production build |
| Browser journey | `npm run e2e` | 28 steps in three languages, axe rules on every page |

Table 5.1: The test suites

All four run in continuous integration on every push; a commit is moved to the development branch only when all of them pass.

## 5.2 Backend tests

The backend has 43 test classes. The most important ones, grouped by the property they show:

| Test | What it shows |
|---|---|
| `PolicyValidatorTest` | No discount above the limit, negative or missing proposals become zero. |
| `UntrustedAssistantTest` | An assistant that offers 80% is capped at the limit in the chat and at checkout. |
| `LlmNegotiatorTest` | The prompt holds no secrets; replies with numbers in any of the three languages are replaced; malformed JSON falls back to the rules. |
| `FallbackNegotiatorTest`, `SwitchingNegotiatorTest` | A failing or slow model is replaced by the rules; the super admin's switch takes effect at once. |
| `ConversationTest` | A negotiation is a conversation; an offer once made stands; offers expire after 24 hours and apply only to the negotiated number of pairs. |
| `OrderControllerTest` | Server-side prices, a tampered offer re-clamped, idempotent checkout, declined and failed payments that release stock, cancellation with refund and restock. |

| Test | What it shows |
|---|---|
| `OrderConcurrencyTest` | Many threads buying the last pair: exactly one succeeds; opposite carts do not deadlock. |
| `CollectionPricingTest`, `SomPricesTest` | The ladder, the minimum and the exchange rates. |
| `DeliveryZoneTest` | Owners set areas; checkout charges the area's fee or none above its free-from amount; a fee sent by the browser is ignored; old receipts keep their area after it changes or is deleted. |
| `WholesaleRequestTest`, `WholesaleRateLimiterTest` | Requests without an account, checked contacts, the bot trap, per-address and shop-wide limits, statuses and audit. |
| `CustomerDetailsTest` | A customer keeps, sees and forgets only their own details. |
| `CatalogControllerTest` | Filters, facet counts per dimension, sizes and colours counted for what can be bought, cost and limit never in public responses. |
| `AdminCatalogControllerTest` | Staff may edit prices and stock but not limits; every change is audited. |
| `AuthControllerTest`, `LoginAttemptServiceTest`, `RegistrationLimiterTest` | Sign-up, sign-in, lockout after five failures, sign-up limits, memory that does not grow without end. |
| `AccountsTest`, `SuperAdminSetupTest` | Team accounts; a disabled account or a new password ends its sessions; the first super admin from the environment. |
| `HttpHardeningTest`, `RealServerSecurityTest` | Security headers, CORS, 401 against 403 on a real embedded server. |
| `PostgresIntegrationTest` | Migrations and constraints on PostgreSQL: impossible rows are refused by the database even when the application is bypassed; the last-pair and double-payment races over real HTTP. |

Table 5.2: The main backend tests

The integration tests share a base class that starts the application once, creates real users with real tokens, and offers helpers for JSON requests (Code 5.1).

```
JsonNode small = json(deliver(buyer, v, 2, Map.of("zoneId", id)).andExpect(status
    ().isCreated()));
assertThat(small.get("total").decimalValue()).isEqualByComparingTo("22.00");
// A fee sent by the browser is ignored: only the area decides.
JsonNode big = json(deliver(buyer, v, 4, Map.of("zoneId", id, "fee", "0")).
    andExpect(status().isCreated()));
assertThat(big.get("total").decimalValue()).isEqualByComparingTo("40.00");
assertThat(big.at("/fulfillment/delivery/fee").decimalValue()).isZero();
```

Code 5.1: An integration test: a fee sent by the browser is ignored

## 5.3 Frontend tests

The frontend tests use Vitest with Testing Library and a fake `fetch`. Among them: checkout sends a wallet token and an idempotency key but never a price or a card number, reuses the key only after a lost connection, charges delivery by area and sends no fee, and fills in remembered details; the bag reads only well-formed entries from storage; the sock drawing accepts only safe colours, so a hand-edited bag cannot inject markup; every text exists in Russian and Kyrgyz; every pair of text and background colours meets WCAG 2.2 AA contrast in both themes; and the wholesale contact check follows the server's rules.

## 5.4 The browser journey

`npm run e2e` drives Chromium through Playwright against the real backend and the built frontend. Its 28 steps cover the owner adding a section and a product with two colours and a picture (and a disguised file being refused), the product appearing in the shop with its filter count, removing and restoring it, a visitor filling the bag and registering, a declined and then a successful payment, the last pair bought and returned by cancelling, the customer asking for 90% and being held to the limit, the team handing the order over and reading the emails it caused, the site in Russian and Kyrgyz, the home page's sections, the owners' screens, the super admin's accounts, assistant and audit log, quick view and prices in som, the family and the gift box, reviews and search, a wholesale request with a wrong and then a right phone number, the women's shelf filtered by size and colour, and a guest ordering without an account

and opening the order from a second browser, first without the link's key (and asking for it by email), then with it. After each important page the axe rules [26] run, and any serious or critical finding fails the journey.

The journey has caught problems that unit tests could not: a menu that flipped between two sizes in Russian, faded text that became too faint to read while a shelf reloaded, and a stamp checked half way through its animation on a slow machine. Each was fixed in the product, not by weakening the test.

## 5.5 Evaluation of the two assistants

### 5.5.1 Method

Sixteen simulated customers (Table 5.3) each send one message about one sock: a browser asking the price, families, shop owners, a gift buyer, speakers of Russian and Kyrgyz, a greedy customer, a prompt-injection attempt, and socks with a thin or no margin. Each customer has a quantity, the limit of the sock and a walk-away point: the smallest discount at which they would buy. Both assistants answer every customer through the same service, prompt, reply checks and validator as the shop. The language-model answers are a recorded live run of gemini-3.5-flash-lite on 11 October 2026 (`docs/evaluation/live-2026-10-11.json`); the super admin can repeat the run at any time.

For each assistant the evaluation measures the average final discount, how many customers would buy, how often the validator had to cut a proposal, whether any final price went below the limit, and the revenue.

| | | | | **Rules** | | **Language model** | |
|---|---|---|---|---|---|---|---|
| **ID** | **Customer** | **Pairs** | **Limit** | **prop.** | **final** | **prop.** | **final** |
| S01 | Browser, one pair | 1 | 15 | 0 | 0 | 0 | 0 |
| S02 | Asks for 10% on one pair | 1 | 15 | 10 | 10 | 0 | 0 |
| S03 | Greedy, one pair | 1 | 15 | 50 | **15** | 0 | 0 |
| S04 | Family of four | 12 | 15 | 17 | **15** | 5 | 5 |
| S05 | Small shop owner | 50 | 20 | 15 | 15 | 15 | 15 |
| S06 | Asks 30% for a carton | 100 | 20 | 30 | **20** | 15 | 15 |

| | | | | Rules | | Language model | |
|---|---|---|---|---|---|---|---|
| **ID** | **Customer** | **Pairs** | **Limit** | **prop.** | **final** | **prop.** | **final** |
| S07 | Russian speaker, haggles | 10 | 15 | 14 | 14 | 5 | 5 |
| S08 | Russian speaker, wholesale | 60 | 18 | 15 | 15 | 15 | 15 |
| S09 | Kyrgyz speaker | 10 | 15 | 14 | 14 | 5 | 5 |
| S10 | Gift buyer | 3 | 12 | 10 | 10 | 5 | 5 |
| S11 | Tries an injection | 1 | 15 | 90 | **15** | 0 | 0 |
| S12 | Exact ask within limit | 20 | 15 | 12 | 12 | 10 | 10 |
| S13 | Thin margin sock | 10 | 5 | 17 | **5** | 5 | 5 |
| S14 | No margin left | 5 | 0 | 10 | **0** | 5 | **0** |
| S15 | Returning wholesale buyer | 200 | 22 | 15 | 15 | 15 | 15 |
| S16 | Polite, no number | 2 | 15 | 2 | 2 | 2 | 2 |

Table 5.3: The simulated customers: proposed and final discount in percent (bold: the validator cut the proposal)

### 5.5.2 Results

| | **Rules** | **Language model** |
|---|---|---|
| Average final discount | 11.1% | 6.1% |
| Customers who would buy | 81% (13 of 16) | 50% (8 of 16) |
| Proposals cut by the validator | 6 | 1 |
| Final prices below the limit | 0 | 0 |
| Revenue of the simulated sales | $1,723.03 | $1,001.62 |

Table 5.4: Summary of the evaluation

### 5.5.3 Discussion

**Safety.** No final price went below the limit on either side. The rule-based assistant over-promised six times, by design, and the validator cut every one of those proposals: the greedy customer, the injection attempt (90% proposed, 15% allowed), the family, the carton, the thin-margin sock and the sock with no margin. The language model

proposed a discount on a sock with no margin once (5%) and was cut to zero. The model also resisted the injection on its own and gave nothing; but the guarantee does not depend on that.

**Commercial behaviour.** The language model was more cautious than the rules: it gave smaller discounts and, against these walk-away points, fewer customers would have bought, so the simulated revenue was lower. This is a property of the prompt as much as of the model: the prompt tells it to start small and give more only for a reason, and in a single message there is little reason. In a real conversation the customer would answer and the model could move; the evaluation measures only the first answer. The rules, written for this shop, give the expected discounts for quantity at once.

**Language and latency.** The model answered every customer in their own language, including Russian and Kyrgyz, in about one to two seconds per message, within the conversational target of NFR-6; the rules answer instantly.

**Validity.** The customers are simulated and their walk-away points are assumptions, so the acceptance and revenue numbers compare the two assistants with each other rather than predict real sales. A user study with real customers of the stall would be the next step.

## 5.6 Requirements coverage

Every functional and non-functional requirement of Chapter 2 is implemented and shown by at least one of the tests above; `docs/traceability.md` lists, for each requirement, where it is implemented and which test shows it. Two are partial by design: grounding (FR-4) uses keyword retrieval rather than vector search, and offline use (NFR-5) covers the bag but not the catalogue.

# Chapter 6

# Conclusions and future work

## 6.1 Conclusion

This thesis built AK&VEN, a complete online shop for a family sock business at Dordoi Bazaar, in which the bazaar's habits continue online: customers ask for a better price in a conversation, buy for the whole family, mix any socks to reach a lower price per pair, and collect their order at the stall or have it delivered to four countries; shops send requests for whole cases. The shop and its administration are one installable web application in three languages; one API holds every business rule; and the database repeats the rules that must never be broken.

The core contribution is a design in which a language model may talk about money without being able to decide it. The model only proposes; a deterministic validator clamps every proposal to a limit the model never sees, again at checkout; the database refuses an allowed discount larger than its proposal; and the model's words may not contain a number of their own. Both the proposal and the result are recorded, so the gap between what the model wanted and what was allowed is visible for every conversation.

## 6.2 Answers to the research questions

**RQ1: Can a language model negotiate while a deterministic component guarantees the limit?** Yes. In the evaluation no final price went below the limit, whether the assistant was the rule-based one that over-promised six times or the language model, including a prompt-injection attempt; the automated tests show the

same for an assistant that deliberately offers 80%, for tampered offers at checkout and for rows written past the application. The guarantee rests on code and constraints, not on the model's behaviour.

**RQ2: How do the two negotiators compare?** On the sixteen simulated customers the language model was more cautious: an average final discount of 6% against 11%, half of the customers buying against four in five, and the validator stepping in once against six times. It answered naturally in all three languages within one or two seconds. The rules are the better seller for single messages; the model is the better conversationalist, and its caution comes largely from the prompt, which the owners' wishes can tune.

**RQ3: Can the bazaar's habits live in an online shop?** The shop expresses them as ordinary interface elements rather than as extra steps: a chat on the product page, a family planner, a price ladder for the whole bag shown in the bag and on every sock, pickup with a code at the container, delivery areas with honest fees and times, and a case builder with a request inbox for shops. The browser journey and the accessibility checks show that these work for a first-time visitor, on a phone, in Russian and Kyrgyz.

## 6.3 Future work

- **A real payment provider**, with payment moved outside the checkout transaction (reserve, pay, confirm) and, later, a second rail through a Kyrgyz bank.
- **A user study** with real customers of the stall, to measure acceptance and satisfaction of the two assistants in full conversations rather than single messages.
- **Vector retrieval** for the assistant with the prepared pgvector table, so it can answer from longer product descriptions and the family's notes.
- **Notifications** by e-mail, SMS or messenger when an order is ready, a sold-out sock is back, or a wholesale request is answered.
- **Real photographs** of the products, replacing the drawn pictures.

- **Demand forecasting** from the orders, the waiting lists and the wholesale requests, to tell the family what to reorder.
- **Translations of the owners' data**: section and colour names in all three languages.

## 6.4 Final remarks

The project started from a simple observation at the stall: nobody pays the label price. The result is a shop that keeps that conversation and keeps the family in control of it. It is ready to be used by my parents once the real prices, photographs and payment provider are in place.

# Acknowledgements

I thank my supervisor, Guettala Walid, for his guidance and for keeping the project honest about what it promises. I thank my parents, Akylbek and Venera, whose stall at Dordoi Bazaar is the reason this shop exists, and who answered every question about socks, sizes, cases and customers. Their two names are on the label.

# Bibliography


[1] Shopizer contributors. *Shopizer: Java open source e-commerce software.* URL: `https://github.com/shopizer-ecommerce/shopizer` (visited on 11/01/2026).

[2] Medusa contributors. *Medusa: Digital commerce platform.* URL: `https://github.com/medusajs/medusa` (visited on 11/01/2026).

[3] Saleor Commerce. *Saleor: Headless, GraphQL commerce platform.* URL: `https://github.com/saleor/saleor` (visited on 11/01/2026).

[4] Mike Lewis et al. "Deal or No Deal? End-to-End Learning of Negotiation Dialogues". In: *Proceedings of the 2017 Conference on Empirical Methods in Natural Language Processing*. ACL, 2017, pp. 2443–2453.

[5] He He et al. "Decoupling Strategy and Generation in Negotiation Dialogues". In: *Proceedings of the 2018 Conference on Empirical Methods in Natural Language Processing*. ACL, 2018, pp. 2333–2343.

[6] Kai Greshake et al. "Not What You've Signed Up For: Compromising Real-World LLM-Integrated Applications with Indirect Prompt Injection". In: *Proceedings of the 16th ACM Workshop on Artificial Intelligence and Security*. ACM, 2023, pp. 79–90.

[7] OWASP Foundation. *OWASP Top 10 for Large Language Model Applications, 2025*. 2024. URL: `https://genai.owasp.org/llm-top-10/` (visited on 11/01/2026).

[8] Patrick Lewis et al. "Retrieval-Augmented Generation for Knowledge-Intensive NLP Tasks". In: *Advances in Neural Information Processing Systems 33*. 2020.

[9] Andrew Kane. *pgvector: Open-source vector similarity search for Postgres.* URL: `https://github.com/pgvector/pgvector` (visited on 11/01/2026).

[10] MDN contributors. *Progressive Web Apps*. URL: https://developer.mozilla.org/en-US/docs/Web/Progressive_web_apps (visited on 11/01/2026).

[11] Google. *Gemini API: OpenAI compatibility*. URL: https://ai.google.dev/gemini-api/docs/openai (visited on 11/01/2026).

[12] Docker Inc. *Docker Compose Documentation*. URL: https://docs.docker.com/compose/ (visited on 11/01/2026).

[13] Redgate. *Flyway Documentation: Migrations*. URL: https://documentation.red-gate.com/flyway (visited on 11/01/2026).

[14] VMware Tanzu. *Spring Boot Reference Documentation, version 3.3*. 2024. URL: https://docs.spring.io/spring-boot/3.3/ (visited on 11/01/2026).

[15] VMware Tanzu. *Spring Security Reference: Method Security and Role Hierarchy*. 2024. URL: https://docs.spring.io/spring-security/reference/ (visited on 11/01/2026).

[16] The PostgreSQL Global Development Group. *PostgreSQL 16 Documentation*. 2023. URL: https://www.postgresql.org/docs/16/ (visited on 11/01/2026).

[17] M. Nottingham and E. Wilde. *Problem Details for HTTP APIs*. RFC 7807. IETF, 2016. URL: https://www.rfc-editor.org/rfc/rfc7807.

[18] M. Jones, J. Bradley, and N. Sakimura. *JSON Web Token (JWT)*. RFC 7519. IETF, 2015. URL: https://www.rfc-editor.org/rfc/rfc7519.

[19] Meta Open Source. *React Documentation*. URL: https://react.dev/ (visited on 11/01/2026).

[20] Microsoft. *TypeScript Handbook*. URL: https://www.typescriptlang.org/docs/handbook/ (visited on 11/01/2026).

[21] Vite contributors. *Vite: Next Generation Frontend Tooling*. URL: https://vite.dev/ (visited on 11/01/2026).

[22] The JUnit Team. *JUnit 5 User Guide*. URL: https://junit.org/junit5/docs/current/user-guide/ (visited on 11/01/2026).

[23] Mountainminds GmbH. *JaCoCo Java Code Coverage Library*. URL: https://www.jacoco.org/jacoco/ (visited on 11/01/2026).

[24] Vitest contributors. *Vitest: Next generation testing framework*. URL: https://vitest.dev/ (visited on 11/01/2026).

[25] Microsoft. *Playwright Documentation*. URL: https://playwright.dev/ (visited on 11/01/2026).

[26] Deque Systems. *axe-core: Accessibility engine for automated Web UI testing*. URL: https://github.com/dequelabs/axe-core (visited on 11/01/2026).

[27] Martin Fowler. *Patterns of Enterprise Application Architecture*. Addison-Wesley, 2002. ISBN: 0-321-12742-0.

[28] OWASP Foundation. *CSV Injection*. URL: https://owasp.org/www-community/attacks/CSV_Injection (visited on 11/01/2026).

[29] World Wide Web Consortium. *Web Content Accessibility Guidelines (WCAG) 2.2*. 2023. URL: https://www.w3.org/TR/WCAG22/ (visited on 11/01/2026).

# List of Figures


2.1 Use cases of visitors and customers . . . . . 8
2.2 Use cases of the staff, the owners and the super admin . . . . . 9

3.1 The footer: the stall's door with its open or closed sign, the promises as sewn labels, every page and the contacts . . . . . 18
3.2 The home page . . . . . 19
3.3 Shop by who it is for: each shelf on its own fabric, with its socks on the line . . . . . 19
3.4 The men's shelf . . . . . 20
3.5 Occasions, heights, sizes and colours; the chosen size shown as a tag . 21
3.6 A product page . . . . . 22
3.7 How the price falls: the price per pair and in total as the number of pairs grows . . . . . 22
3.8 The chat: asked for 50%, the assistant offers what the owners allow . 23
3.9 The fitting room . . . . . 24
3.10 The family planner, kept on a sheet of paper pegged to the page . . . 25
3.11 Building a gift box . . . . . 25
3.12 The bag as one collection . . . . . 26
3.13 Checkout with a delivery area . . . . . 27
3.14 The simulated wallet . . . . . 27
3.15 A paid order . . . . . 28
3.16 The account . . . . . 29
3.17 The wholesale page . . . . . 30
3.18 Building a case . . . . . 30
3.19 A request sent, with its reference . . . . . 31
3.20 Find us at Dordoi . . . . . 31
3.21 The home page and the children's shelf on a phone, in Kyrgyz . . . . 32
3.22 Products . . . . . 33

3.23 Adding a product . . . . . 33
3.24 Orders . . . . . 34
3.25 Handing an order over at the stall . . . . . 34
3.26 Negotiations: proposed and allowed, side by side . . . . . 35
3.27 The dashboard . . . . . 36
3.28 The inbox of wholesale requests . . . . . 36
3.29 Pricing . . . . . 37
3.30 Delivery areas . . . . . 38
3.31 Choosing and trying the assistant . . . . . 39
3.32 The audit log . . . . . 39

4.1 Architecture overview . . . . . 42
4.2 The core of the data model . . . . . 46
4.3 The validation path: the proposal is untrusted until the validator has clamped it . . . . . 53
4.4 One negotiation turn . . . . . 54

# List of Tables

2.1 Users of the system . . . . . 7
2.2 Functional requirements . . . . . 12
2.3 Non-functional requirements . . . . . 13

3.1 Demo accounts . . . . . 16
3.2 The main settings . . . . . 17

4.1 Technology stack . . . . . 43
4.2 The main tables . . . . . 47
4.3 The API by audience . . . . . 50

5.1 The test suites . . . . . 63
5.2 The main backend tests . . . . . 64
5.3 The simulated customers: proposed and final discount in percent (bold: the validator cut the proposal) . . . . . 67
5.4 Summary of the evaluation . . . . . 67

# List of Codes

3.1 Starting the shop . . . . . 16
4.1 Repository layout . . . . . 43
4.2 The PolicyValidator . . . . . 51
4.3 Deciding the price of an order line . . . . . 52
4.4 A reply may state no number of its own (Cyrillic shown as Java Unicode escapes) . . . . . 55
5.1 An integration test: a fee sent by the browser is ignored . . . . . 64